

BAYSIDE HEALTH SYSTEM

St. Anselm Medical Center - East Patient Tower Addition

Project Manual, Volume 1, Division 01 (Issued for Construction, 2026-04-15)

SECTION 01 35 23 - OWNER SAFETY REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS: Drawings and general provisions of the Contract, including General and Supplementary Conditions, apply to this Section.

1.3.A. Contractor shall comply with the Owner's Contractor Safety Rules and with OSHA 29 CFR 1926; the more stringent governs.

1.3.B. All contractor personnel shall wear an Owner-issued construction badge while on the campus.

1.4.A. No crane load shall pass over any occupied building. Loads over an unoccupied portion require an Owner-approved lift plan and a cleared zone.

1.4.B. Contractor subcontractors shall have an EMR of 1.10 or less; exceptions require written Owner approval.

1.5.A. Utility shutdowns affecting the hospital require a Utility Shutdown Request submitted 14 calendar days in advance and approved by the Director of Facilities & Construction.

1.5.B. Any impairment of fire alarm, sprinkler or smoke control systems requires an Owner-approved impairment notice and interim life safety measures (ILSM) per The Joint Commission LS.01.02.01 and NFPA 101.

1.6.A. Noise at the nearest occupied patient room shall not exceed 70 dBA between 07:00 and 19:00 and 55 dBA at other times; vibration-generating work next to surgery requires 48 hours' notice.

1.7.A. Emergency exits, ambulance routes and fire lanes shall remain unobstructed at all times.

1.8.A. The Contractor shall report any injury or near miss on the campus to the Owner's Safety Officer within 2 hours.

PART 2 - PRODUCTS (Not used)

PART 3 - EXECUTION (Not used)

END OF SECTION 01 35 23

SECTION 01 35 13.13 - INFECTION CONTROL DURING CONSTRUCTION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS: Drawings and general provisions of the Contract, including General and Supplementary Conditions, apply to this Section.

1.2.A. An Infection Control Risk Assessment (ICRA) shall be completed with the Owner's Infection Prevention department for each area of work, using the ASHE ICRA 2.0 matrix, and an ICRA permit issued before work begins.

1.3.A. Class III and IV: rigid barriers from floor to deck, sealed; negative pressure of at least -0.01 in. w.c. continuously monitored with an alarmed manometer and recorded daily; HEPA filtration of exhaust.

1.3.B. Class IV: an anteroom is required; workers wear shoe covers and coveralls that are removed on exit.

1.4.A. Barriers shall be inspected daily by the Contractor and weekly by Infection Prevention. Any breach shall stop work until repaired and re-inspected.

1.5.A. Debris shall be removed in covered carts by designated routes and times approved by the Owner.

PART 2 - PRODUCTS (Not used)

PART 3 - EXECUTION (Not used)

END OF SECTION 01 35 13.13